

ADDENDUM NO.3
2025 REPLACEMENT FENCE FOR RHINEBECK LITTLE LEAGUE FIELD BID
BID #01-2025
April 02, 2025

Revised Specs for little league field fences

The following addendum including changes, additions and/or deletions are hereby made a part of this bid. All changes will be noted in red.

Removal and disposal of existing fencing and concrete and holes filled by customer

Install +-564' of 4' high All Black Chain Link System (outfield fence)

- 2" x 8ga. Black Vinyl-Coated KK fabric
- SS40 Powder-Coated Black framework
- 1-5/8" PC top-rail and gate frames
- 2" PC line posts max 10' on-center (10" x 36" holes)
- 2.5" PC terminal and gate posts (10" x 36" holes)
- All posts set in concrete footings (3,000-4,000 psi)
- 7ga. VC spring-coil bottom tension wire
- 9ga. VC steel fence ties & hog-rings
- (2) @ 3" x 20' high foul poles (10" x 36" holes)
- (2) @ 10' wide double drive gate
- (1) @ 4' wide walk gate
- Box hinges and fulcrum latches
- 4" "Polycap" or similar fence topper in yellow (installed)

Install +-200' of 8' high + 12' high nylon netting All Black Chain Link System (dugout/sideline fences)

- 2" x 8ga. Black Vinyl-Coated KK fabric
- SS40 Powder-Coated Black framework
- 1-5/8" PC top, mid, and bottom rail and gate frames
- 2.5" PC line posts max 10' on-center (10" x 36" holes)
- **Four (4) x 2 @ 4" x 20' high terminal and intermediate posts for netting (12" x 48" holes)**
- All posts set in concrete footings (3,000-4,000 psi)
- 9ga. VC steel fence ties
- (2) @ 4' wide x 8' high walk gate
- Box hinges and fulcrum latches
- 12' high twisted #36 nylon netting to bring overall height to 20' high
 - 1.75" square
 - Sewn hem with grommets every 18"
 - Stainless Steel aircraft cabling

Install +-52' of 6' high All Black Chain Link System (on deck area)

- 2" x 8ga. Black Vinyl-Coated KK fabric
- SS40 Powder-Coated Black framework
- 1-5/8" PC top, mid, and bottom rail and gate frames
- 2" PC line posts max 10' on-center (10" x 36" holes)
- 2.5" PC terminal and gate posts (10" x 36" holes)
- All posts set in concrete footings (3,000-4,000 psi)
- 9ga. VC steel fence ties
- (2) @ 4' wide walk gate
- Box hinges and fulcrum latches

Install +-60' of 20' high All Black Chain Link System (Straight up Backstop)

- 2" x **6ga.** x 12' high Black Vinyl-Coated KK fabric
- 2" x **8ga.** x 8' high Black Vinyl-Coated KK fabric
- SS40 Powder-Coated Black framework
- 1-5/8" PC top, bottom and mid rails (4)

- 4" posts set in concrete footings (12" x 48" holes) (3,000-4,000 psi)

Also please provide in bid submission a copy of NYS Department of Labor Contractor Registration Certificate(Certificate of registration)(see section 14 under "General Conditions" in original bid)